

GENERAL NOTES:


1. NEW PIPING AND EQUIPMENT IS DRAWN WITH A HEAVY LINE AND EXISTING ITEMS ARE DRAWN WITH A LIGHT LINE.
2. ALL WORK AND MATERIALS SHALL COMPLY WITH INTERNATIONAL CODES AND UCB CONSTRUCTION STANDARDS.
3. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS PRIOR TO BID. AND SHALL VERIFY PIPE SIZES, DIMENSIONS, VOLTAGES, ETC, PRIOR TO CONSTRUCTION.
4. INSTALL NEW PIPING AND EQUIPMENT TO BE ACCESSIBLE FOR SERVICE AND MAINTENANCE WITHOUT OBSTRUCTING EXISTING DEVICES NEEDING SERVICE AND MAINTENANCE.
5. CONTRACTOR SHALL ENSURE THAT NEW PIPING AND EQUIPMENT WILL NOT OBSTRUCT THE SPRAY PATTERN OF ANY FIRE SPRINKLERS.
6. CONTRACTOR SHALL PROTECT FIRE SPRINKLERS IN THE CONSTRUCTION AREA AGAINST MECHANICAL DAMAGE.
7. CONTRACTOR SHALL OBTAIN A HOT WORK PERMIT FOR ANY WORK INVOLVING HEAT GUNS, SOLDERING, BRAZING, WELDING, GRINDING, POWDER DRIVEN STUD, METAL CUTTING USING POWER TOOLS OR OTHER ACTIVITIES INVOLVING FLAMES OR SPARKS. HOT WORK PERMIT FORMS ARE AVAILABLE FROM CU PROJECT MANAGERS, FM OFFICE OF PLANNING, DESIGN AND CONSTRUCTION AND UNDER "HOT WORK PERMIT" AT THE FLS WEB SITE: ([HTTP://WWW.COLORADO.EDU/FACILITIESMANAGEMENT/PDC/SAFETY/INDEX.HTML](http://www.colorado.edu/facilitiesmanagement/pdc/safety/index.html)).
8. AT ALL TIMES, CONTRACTOR SHALL ENSURE THAT THE PROJECT AND STAGING AREA AND CONSTRUCTION ACTIVITIES DO NO CAUSE OBSTRUCTION OF EGRESS PATHS INSIDE THE BUILDING, BLOCK EXIT DISCHARGE FROM THE BUILDING OR IMPEDE EMERGENCY VEHICLE ACCESS TO THE AREA.
9. IF THE CONSTRUCTION ACTIVITIES GENERATE DUST OF FUMES INSIDE THE BUILDING, CONTRACTOR SHALL TAKE NECESSARY MEASURES TO PREVENT NUISANCE ACTUATION OF ANY NEARBY SMOKE OR DUCT DETECTORS. CONTACT THE FIRE SYSTEMS GROUP FOR ASSISTANCE IN ADVANCE OF THESE ACTIVITIES.
10. OUTAGE PROCEDURES: CONTRACTOR SHALL FOLLOW CAMPUS PROCEDURES FOR ANY OUTAGE OF FIRE SYSTEMS. THE CAMPUS PROCEDURES ARE AVAILABLE FROM THE FLS WEB SITE: ([HPPT://WWW.COLORADO.EDU/FACILITIESMANAGEMENT/PDC/SAFETY/DOCUMENTS/FIRE_SUPPRESSION_SYSTEMS.PDF](http://www.colorado.edu/facilitiesmanagement/pdc/safety/documents/fire_suppression_systems.pdf)) AND ([HTTP://WWW.COLORADO.EDU/FACILITIESMANAGEMENT/PDC/SAFETY/DOCUMENTS/FIREALARM_DETECTION.PDF](http://www.colorado.edu/facilitiesmanagement/pdc/safety/documents/firealarm_detection.pdf))
11. CONTRACTOR SHALL MAKE SURE THAT NEW WORK SHALL NOT BLOCK ACCESS TO ANY OF THE EXISTING INFORMATION TECHNOLOGY OUTLETS OR PATHWAYS INCLUDING BUT NOT LIMITED TO CABLE TRAYS, PULL BOXES, BUTTERS, WIRE MOLD, ETC.

UNIVERSITY OF COLORADO AT BOULDER

MAIN CAMPUS SMART METERING CAMP CP 142558

SMART GRID
METERING 2011
University of Colorado at Boulder
Boulder, Colorado

Revision Date Description By



KEY PLAN

BID SET

SHEET INDEX:

T1	TITLE SHEET
ME1.0	MECHANICAL/ ELECTRICAL LEGEND & ABBREVIATIONS
M1.0	CIRES BUILDING - MECHANICAL
M2.0	EKELEY BUILDING - MECHANICAL
M3.0	MCDB BUILDING - MECHANICAL
M4.0	MUENZINGER BUILDING - MECHANICAL
M5.0	IMIG MUSIC BUILDING - MECHANICAL
M6.0	PORTER BUILDING - MECHANICAL
M7.0	MECHANICAL DETAILS
M7.1	MECHANICAL DETAILS
E1.0	CIRES BUILDING - ELECTRICAL
E2.0	EKELEY BUILDING - ELECTRICAL
E3.0	MCDB BUILDING - ELECTRICAL
E4.0	MUENZINGER BUILDING - ELECTRICAL
E5.0	IMIG MUSIC BUILDING - ELECTRICAL
E6.0	PORTER BUILDING - ELECTRICAL
E7.0	PANELBOARD SCHEDULES
E7.1	ELECTRICAL DETAILS
E7.2	ELECTRICAL DETAILS

Ulteig

Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JJB
Checked By: NHM
Approved By: NHM

TITLE SHEET

Project Number: 10.01461
Date: 07/08/2011
Sheets: 1 of 19

T1

ELECTRICAL SYMBOLS LEGEND					
THIS IS A COMPREHENSIVE SYMBOL SCHEDULE. NOT ALL SYMBOLS ARE APPLICABLE TO THESE DRAWINGS					
SYMBOLS	DESCRIPTION	MOUNTING HEIGHT TO CENTER OF DEVICE UNLESS OTHERWISE INDICATED	SYMBOLS	DESCRIPTION	MOUNTING HEIGHT TO CENTER OF DEVICE UNLESS OTHERWISE INDICATED
	CEILING SURFACE MOUNTED LIGHT FIXTURE. CAPITAL LETTER INDICATES FIXTURE TYPE. SMALL LETTER INDICATES SWITCHING.			ENCLOSED MOLDED CASE CIRCUIT BREAKER 30A/2P ION (WALL RECESSED)	
	RECESSED CEILING MOUNTED LIGHT FIXTURE			VARIABLE FREQUENCY CONTROLLER	
	WALL MOUNTED INCAND. OR H.I.D. LIGHT FIXTURE. SURFACE OR RECESSED MOUNTED.			THERMAL SWITCH (MOTOR OVERLOAD TYPE)	48 INCHES
	CEILING MOUNTED JUNCTION BOX ("C" INDICATES EMERGENCY CRITICAL BRANCH POWER. "L" INDICATES EMERGENCY LIFE SAFETY POWER. "E" INDICATES EMERGENCY EQUIPMENT POWER)	18 INCHES		THERMOSTAT - PROVIDED BY DIVISION 25	48 INCHES
	WALL JUNCTION BOX			THERMOSTAT - FURNISHED BY DIVISION 23, INSTALLED BY DIVISION 25	48 INCHES
	CEILING EXIT SIGN. SHADED SIDE INDICATES LIGHTED FACE. ARROWS INSTALLED AS SHOWN	6 INCHES ABOVE DOOR FRAME TO BOTTOM		HASH MARKS INDICATE ITEM NOTED TO BE REMOVED	
	WALL EXIT SIGN			SPEAKER	
	SUSPENDED FIXTURE			WALL MOUNTED SPEAKER	50 INCHES TO BOTTOM
	SURFACE FLUORESCENT			CLOCK	54 INCHES TO BOTTOM
	RECESSED FLUORESCENT			MICROPHONE OUTLET	18 INCHES
	FIXTURE CONNECTED TO EMERGENCY POWER			VOLUME CONTROL	48 INCHES
	EMERGENCY BATTERY LIGHT	7 FOOT 6 INCHES		SECURITY DEVICES: REQUEST TO EXIT	3 INCHES ABOVE DOOR FRAME
	EMERGENCY REMOTE LAMP	7 FOOT 6 INCHES		DOOR POSITION SWITCH, RECESSED	
	SWITCH: SINGLE POLE (HORSEPOWER RATED WHEN USED AS MOTOR DISCONNECT)	48 INCHES		DOOR POSITION SWITCH, SURFACE MOUNT	
	DOUBLE POLE	48 INCHES		DOOR POSITION SWITCH	
	3-WAY	48 INCHES		CARD READER	48 INCHES
	4-WAY	48 INCHES		CEILING MOUNTED MOTION SENSOR SWITCH	
	KEY OPERATED	48 INCHES		CEILING MOUNTED MOTION SENSOR SWITCH, 90° COVERAGE	
	WITH PILOT LIGHT (CAN BE USED WITH OTHER SWITCH TYPES)	48 INCHES		CEILING MOUNTED MOTION SENSOR SWITCH, 180° COVERAGE	
	FLUORESCENT DIMMER	48 INCHES		CEILING MOUNTED MOTION SENSOR SWITCH, 360° COVERAGE	
	MOMENTARY CONTACT DIMMER (600 WATT UNLESS OTHERWISE NOTED)	48 INCHES		CEILING MOUNTED MOTION SENSOR SWITCH, HALLWAY COVERAGE	
	LIGHTING INTENSITY SELECTOR	48 INCHES		WALL MOUNTED MOTION SENSOR, 90° COVERAGE	
	LOW VOLTAGE SWITCH	48 INCHES		WALL MOUNTED MOTION SENSOR, 180° COVERAGE	48 INCHES
	DUPLEX RECEPTACLE	18 INCHES		MOTION SENSOR SWITCH POWER PACK	
	DOUBLE DUPLEX RECEPTACLE	18 INCHES		AUXILIARY INPUT OUTLET	18 INCHES
	SPECIAL PURPOSE RECEPTACLE (LETTER INDICATES TYPE. SEE SPECIFICATION)	18 INCHES		COMPUTER/TELEPHONE OUTLET (NUMBER INDICATES QUANTITY OF CABLES AND JACKS. NO NUMBER INDICATES ONE)	18 INCHES
	MULTI-OUTLET ASSEMBLY - M.O.A. - PROVIDE DEVICES AS SHOWN ON PLANS	18 INCHES		COMBINATION COMPUTER/TELEPHONE OUTLET (IN SINGLE GANG OPENING) (NUMBER INDICATES QUANTITY OF CABLES AND JACKS. NO NUMBER INDICATES ONE)	18 INCHES
	DUPLEX RECEPTACLE, HALF SWITCHED	18 INCHES		TELEPHONE OUTLET ("W" INDICATES WALL MOUNTED AT 48 INCHES)	18 INCHES
	FLOOR OUTLET, ADDITIONAL SYMBOL INDICATES TYPE			DATA PATCH PANEL	
	TIME SWITCH			COMPUTER/TELEPHONE OUTLET, PROVIDE ROUGH-IN AND CONDUIT ONLY	18 INCHES
	PHOTO CELL			TELEVISION OUTLET	18 INCHES
	TRANSFORMER			INTERCOM OUTLET	18 INCHES
	FIRE ALARM, MANUAL STATION	48 INCHES		INTERCOM MASTER	
	RATE OF RISE DETECTOR			INTERCOM STAFF STATION	
	FIXED TEMPERATURE DETECTOR			BUZZER	
	DUCT PHOTOELECTRIC DETECTOR			PUSH BUTTON	42 INCHES
	PHOTOELECTRIC DETECTOR ("S" INDICATES SLEEPING ROOM WITH ALIX. CONTACT. "G" INDICATES WITH GUARD. "E" INDICATES FOR ELEVATOR RECALL)			POWER DOOR HANDICAP PUSH PAD	
	COMBINATION HEAT/SMOKE WITH STROBE SOUNDER BASE DETECTOR			BELL	
	COMBINATION FIRE/SMOKE DAMPER OR SMOKE DAMPER BY DIVISION 23			CONTACTOR (NUMBER INDICATES NUMBER OF POLES)	
	HORN ("S" INDICATES WITH STROBE LIGHT)	BOTTOM OF LENS 80 INCHES		WEATHERPROOF	
	SPEAKER HORN ("S" INDICATES WITH STROBE LIGHT)	BOTTOM OF LENS 80 INCHES		ABOVE COUNTER	
	CHIME ("S" INDICATES WITH STROBE LIGHT)	BOTTOM OF LENS 80 INCHES		ELECTRIC WATER COOLER	
	FIRE ALARM MODULE/RELAY			NURSE CALL: CORRIDOR CALL OR ZONE LIGHT	
	FAN RELAY			MASTER STATION	
	STROBE LIGHT	BOTTOM OF LENS 80 INCHES		PATIENT EMERGENCY STATION	48 INCHES
	MAGNETIC DOOR HOLD OPEN			STAFF STATION	48 INCHES
	INTEGRAL MAGNETIC DOOR CLOSER (PROVIDED BY DIVISION 08)			DUTY STATION	48 INCHES
	TAMPER SWITCH (NUMBER INDICATES NUMBER OF DEVICES AT THIS LOCATION)			DOUBLE BED PATIENT STATION	
	FIRE PUMP			EMERGENCY (CODE BLUE)	
	FLOW SWITCH			NURSE LOCATOR	
	FIRE ALARM CONTROL PANEL			STAFF ASSIST	48 INCHES
	FIRE ALARM ANNUNCIATOR			STAFF REGISTER	
	LIGHTING AND APPLIANCE PANELBOARD			EMERGENCY PUSH BUTTON	48 INCHES
	SWITCHBOARD OR MOTOR CONTROL CENTER AS NOTED			UNIT INTERFACE	
	CONTROL CABINET BY DIVISION 23			TELEMETRY ANTENNA	
	SPECIAL EQUIPMENT CABINET AS NOTED			CONDUIT CONCEALED IN WALL OR CEILING. QUANTITY OF CONDUCTORS NOT SHOWN. PROVIDE AS REQUIRED FOR DEVICE/CIRCUIT NUMBERS SHOWN.	
	POWER POLE			CONDUIT UP	
	MOTOR (NUMBER REFERS TO MOTOR AND EQUIPMENT SCHEDULE. SEE SCHEDULE FOR WIRING AND CONTROL REQUIREMENTS)			CONDUIT DOWN	
	DISCONNECT ("F" INDICATES FUSED WHEN SHOWN)			CONDUIT CONCEALED IN FLOOR	
	MAGNETIC STARTER			HOME RUN TO PANELBOARD. QUANTITY OF CONDUCTORS REQUIRED NOT INDICATED. PROVIDE QUANTITY AS REQUIRED FOR CIRCUIT NUMBERS SHOWN. SWITCHING ARRANGEMENT, OR NUMBER OF HOME RUNS SHOWN. #10 INDICATES WIRE SIZE. NO NUMBERS INDICATES #12, 3/4 INCH CONDUIT MINIMUM.	
	COMBINATION STARTER-DISCONNECT			SURFACE CONDUIT OR SURFACE RACEWAY	
	UL 924 RELAY			WIRE BASKET TYPE CABLE TRAY	
	NOTE IDENTIFICATION			COMMUNICATIONS CABLE SUPPORT HANGER	
				LIGHTING CIRCUIT DESIGNATION AND PLAN NOTE REFERENCE NUMBER	
				LIGHTING CIRCUIT DESIGNATION	

NOTES:
1. FOR DEVICES SHOWN AS 48 INCHES MOUNTING HEIGHT, WHEN INSTALLED IN MASONRY BLOCK WALLS, MOUNTING AT 48 INCHES TO THE TOP OF THE OUTLET BOX IS ACCEPTABLE.

MECHANICAL SYMBOLS & ABBREVIATIONS LEGEND			
THIS IS A COMPREHENSIVE SYMBOL SCHEDULE. NOT ALL SYMBOLS ARE APPLICABLE TO THESE DRAWINGS			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	HWS - HOT WATER SUPPLY		BALL VALVE INDICATOR
	HWR - HOT WATER RETURN		CHECK VALVE, ARROW IN DIRECTION OF FLOW
	CWS - CHILLED WATER SUPPLY		2-WAY TEMPERATURE CONTROL VALVE
	CWR - CHILLED WATER RETURN		3-WAY TEMPERATURE CONTROL VALVE
	LPS - LOW PRESSURE STEAM		STRAINER
	LPC - LOW PRESSURE CONDENSATE		BALANCING VALVE
	MP/ST/M - MEDIUM PRESSURE STEAM		BACKFLOW PREVENTER
	MPC - MEDIUM PRESSURE CONDENSATE		FLOW SWITCH
	HPS - HIGH PRESSURE STEAM		PRESSURE REDUCING VALVE
	HPC - HIGH PRESSURE CONDENSATE		PRESSURE GAUGE
	LFS - LOOP FIELD SUPPLY		SOLENOID VALVE
	LFR - LOOP FIELD RETURN		THERMOMETER
	PC - PUMPED CONDENSATE		UNION
			FLEXIBLE PIPE CONNECTION
			CAPPED PIPE
			AIR VENT
			REDUCER, CONCENTRIC
			REDUCER, ECCENTRIC
			STEAM TRAP
			BUTTERFLY VALVE
			GLOBE VALVE
			GATE VALVE
			WATER FLOW MEASURING DEVICE
			AUTOMATIC FLOW CONTROL VALVE
			CONNECT NEW TO EXISTING
			DEMOLITION NOTE
			KEY NOTE

UNIVERSITY OF COLORADO
Post Commissioning Check Out For Andover Controls Commissioning

Andover Controls Commissioning Documentation
Preconstruction / Post Construction Commissioning
Rev. 1.1
17-Oct-07

Project Manager: _____

Work Order #: _____

Building Location: _____

Contractor: _____

Commissioning: Complete Incomplete

If complete - Signature of Commissioning Agent: _____
Date: _____

Panel layouts in enclosure: Yes No

If Yes - Signature of Verifying UCB Staff: _____
Date: _____

Submittals: Handed Over to UCB Staff or Still in Possession

If Submittals Are Handed Over to UCB Staff - Signature of Recipient of Submittals: _____
Date: _____

Alarms Created and Implemented: Yes No

Final Approval of Completed Job

Andover Technician 1: _____ **Date:** _____

Andover Technician 2: _____ **Date:** _____

Shop Supervisor: _____ **Date:** _____

Facilities Management
HVAC Control Shop
Shop Phone: 303-492-8056
Fax Number: 303-492-8056

UNIVERSITY OF COLORADO
Preconstruction / Post Construction Commissioning Check out for Andover Controls

Andover Controls Commissioning Documentation
Preconstruction / Post Construction Commissioning
Rev. 1.1
17-Oct-07

Date of Request: _____

Project Manager: _____

Work Order #: _____

Building Location: _____

Contractor: _____

Are new controllers being added? Yes No
If Yes, how many? _____

Will an Infilink / Repeater be required? Yes No
If Yes, Where and or how many? _____

Is there an existing controller being modified? Yes No
If Yes, Existing controller Name: _____
Controller Serial Number: _____
Points to be added or removed: _____

Programs Modified: _____

Other: _____
Example: Addition of expansion module, point rearrangement, etc.

Reviewed and Approved By:

Andover Technician 1: _____ **Date:** _____

Andover Technician 2: _____ **Date:** _____

Shop Supervisor: _____ **Date:** _____

**SMART GRID
METERING 2011**
University of Colorado at Boulder
Boulder, Colorado

Revision	Date	Description	By

Due to the rapid growth and complexity of the University's Andover DDC Control System, this procedure must be followed and adhered to in order to ensure all additions and alterations are documented and accounted for.

Failure to complete the following forms will result in denial of connectivity to the campus Andover network and in violation of UCB Standards 15950 Section 3.04, Detail A.02 and Detail A.03.

KEY PLAN

BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JJB
Checked By: NHM
Approved By: NHM

**MECHANICAL AND
ELECTRICAL LEGEND
AND ABBREVIATIONS**

MECHANICAL/PLUMBING METERING INFORMATION MATRIX											
METER SYSTEM	MANUFACTURER	MODEL NO.	SERIAL NO.	PIPE/LINE SIZE (INCHES)	METER SIZE (INCHES)	CAPACITY (FLOW RANGE)	INSTALLATION DATE	OLD METER READING	NEW METER READING	METER LOCATION	REMARKS
DOMESTIC COLD WATER	ONICON	F-3100		2	2	1.0-345				1B A-1	1, 2, 3
HIGH PRESSURE STEAM	VERIS	ACCELBAR		2	2	0.071-1,000				TUNNEL T3-G	1, 2, 3
CHILLED WATER	ONICON	F-3500		3	3	2.4-460				1B A-1	1, 2, 3

GENERAL NOTES:

- SERIAL NUMBER AND INSTALLATION DATE COLUMN FOR EACH METER SHALL BE COMPLETED BY CONTRACTOR FOLLOWING METER INSTALLATION AND PRIOR TO TURN OVER TO UNIVERSITY.
- PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
- MOUNT METER HORIZONTALLY.
- MOUNT METER VERTICALLY.
- REMOTE SENSOR HEAD LOCATION.

**SMART GRID
METERING 2011**
University of Colorado at Boulder
Boulder, Colorado



Revision Date Description By

SHEET NOTES:

- NEW CONDENSATE METER. WIRE TO NEW KEEP PANEL.
- NEW 2" DOMESTIC WATER METER. WIRE TO NEW KEEP PANEL.
- REPLACE CHILLED WATER METER AND CONTROLLER. WIRE TO NEW KEEP PANEL.
- NEW KEEP PANEL.
- REMOVE EXISTING CHILLED WATER METER PANEL, AND ASSOCIATED WIRING.


GENERAL NOTES:

- FOR DRAWING CLARITY NOT ALL PIPING AND EQUIPMENT HAS NOT BEEN SHOWN.
- FIELD VERIFY EXISTING CONDITIONS BEFORE COMMENCEMENT OF WORK OR ORDERING MATERIALS.



KEY PLAN

BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JJB
Checked By: NHM
Approved By: NHM

CIRES BUILDING

Project Number: 10.01461
Date: 07/08/2011
Sheets: 3 of 19

M1.0

MECHANICAL/PLUMBING METERING INFORMATION MATRIX											
METER SYSTEM	MANUFACTURER	MODEL NO.	SERIAL NO.	PIPE/LINE SIZE (INCHES)	METER SIZE (INCHES)	CAPACITY (FLOW RANGE)	INSTALLATION DATE	OLD METER READING	NEW METER READING	METER LOCATION	REMARKS
DOMESTIC COLD WATER	ONICON	F-3100		4	4	4-1,311				M2B51D	1, 2, 3
HIGH PRESSURE STEAM	VERIS	ACCELABAR		6	6	0.68-29,200				M2B10	1, 2, 3
CHILLED WATER	ONICON	F-3500		8	8	39-3,100				M2B51D	1, 2, 3




GENERAL NOTES:
 1. SERIAL NUMBER AND INSTALLATION DATE COLUMN FOR EACH METER SHALL BE COMPLETED BY CONTRACTOR FOLLOWING METER INSTALLATION AND PRIOR TO TURN OVER TO UNIVERSITY.
 2. PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
 3. MOUNT METER HORIZONTALLY
 4. MOUNT METER VERTICALLY
 5. REMOTE SENSOR HEAD LOCATION.

SHEET NOTES:

- 1 NEW HIGH PRESSURE STEAM METER. WIRE TO NEW KEP PANEL.
- 2 REPLACE DOMESTIC WATER METER. WIRE TO NEW KEP PANEL.
- 3 NEW CHILLED WATER METER AND CONTROLLER. WIRE TO NEW KEP PANEL.
- 4 NEW KEP PANEL.
- 5 EXISTING AND/OVER CONTROL PANELS.


GENERAL NOTES:

- 1. FOR DRAWING CLARITY NOT ALL PIPING AND EQUIPMENT HAS NOT BEEN SHOWN.
- 2. FIELD VERIFY EXISTING CONDITIONS BEFORE COMMENCEMENT OF WORK OR ORDERING MATERIALS.



KEY PLAN

BID SET



Ulteig
 Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
 9777 Pyramid Court #200
 Englewood, Colorado 80112
 Phone: 720.873.5700 Fax: 720.873.5701
 Web: www.ulteig.com
 Drawn By: JJB
 Checked By: NHM
 Approved By: NHM

EKELEY BUILDING

MECHANICAL/PLUMBING METERING INFORMATION MATRIX											
METER SYSTEM	MANUFACTURER	MODEL NO.	SERIAL NO.	PIPE/LINE SIZE (INCHES)	METER SIZE (INCHES)	CAPACITY (FLOW RANGE)	INSTALLATION DATE	OLD METER READING	NEW METER READING	METER LOCATION	REMARKS
DOMESTIC COLD WATER	ONICON	F-3100		6	6	9.0-2,975				A4 B10	1, 2, 3
HIGH PRESSURE STEAM	VERIS	ACCELBAR		6	6	0.58-20,400				CR A4 B01	1, 2, 3
CHILLED WATER	ONICON	F-3500		12	12	35-7,050				A4 B40	1, 2, 3


GENERAL NOTES:
 1. NEW GATE VALVE NOT REQUIRED FOR NEW STEAM METER.
 2. SERIAL NUMBER AND INSTALLATION DATE COLUMN FOR EACH METER SHALL BE COMPLETED BY CONTRACTOR FOLLOWING METER INSTALLATION AND PRIOR TO TURN OVER TO UNIVERSITY.
 3. PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
 4. MOUNT METER HORIZONTALLY
 5. MOUNT METER VERTICALLY.
 6. REMOTE SENSOR HEAD LOCATION.



1



2



3





3

SHEET NOTES:

- 1 REPLACE HIGH PRESSURE STEAM METER. WIRE TO NEW KEP PANEL. REMOVE EXISTING STEAM METER PANEL.
- 2 REPLACE DOMESTIC WATER METER. WIRE TO NEW KEP PANEL.
- 3 REPLACE EXISTING CHILLED WATER METER AND REMOVE CONTROLLER. EXTEND CONTROL OUTPUT TO NEW KEP PANEL.
- 4 NEW KEP PANEL.
- 5 EXISTING AND/OVER CONTROL PANELS.
- 6 REMOVE EXISTING STEAM METER PANEL AND ASSOCIATED WIRING.

GENERAL NOTES:

- 1. FOR DRAWING CLARITY NOT ALL PIPING AND EQUIPMENT HAS NOT BEEN SHOWN.
- 2. FIELD VERIFY EXISTING CONDITIONS BEFORE COMMENCEMENT OF WORK OR ORDERING MATERIALS.



KEY PLAN NORTH

BID SET




Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
 9777 Pyramid Court #200
 Englewood, Colorado 80112
 Phone: 720.873.5700 Fax: 720.873.5701
 Web: www.ulteig.com
 Drawn By: JJB
 Checked By: NHM
 Approved By: NHM

MCDB BUILDING




MECHANICAL/PLUMBING METERING INFORMATION MATRIX											
METER SYSTEM	MANUFACTURER	MODEL NO.	SERIAL NO.	PIPE/LINE SIZE (INCHES)	METER SIZE (INCHES)	CAPACITY (FLOW RANGE)	INSTALLATION DATE	OLD METER READING	NEW METER READING	METER LOCATION	REMARKS
DOMESTIC COLD WATER	ONICON	F-3100		4	4	4.0-1,311				D0065	1, 2, 3
HIGH PRESSURE STEAM	VERIS	ACCELABAR		8	6	0.68-29,200				TUNNEL T	1, 2, 3, 5
CHILLED WATER	ONICON	F-3500		8	8	16-3,100				TUNNEL T	1, 2, 4

GENERAL NOTES:
 1. SERIAL NUMBER AND INSTALLATION DATE COLUMN FOR EACH METER SHALL BE COMPLETED BY CONTRACTOR FOLLOWING METER INSTALLATION AND PRIOR TO TURN OVER TO UNIVERSITY.
 2. PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
 3. MOUNT METER HORIZONTALLY.
 4. MOUNT METER VERTICALLY.
 5. REMOTE SENSOR HEAD LOCATION.



2 NORTH M4.0 0 4 8 16' MUENZINGER SECOND BASEMENT LEVEL NEW




2 NORTH M4.0 0 4 8 16' MUENZINGER SECOND BASEMENT TUNNEL SECTION

SMART GRID METERING 2011
 University of Colorado at Boulder
 Boulder, Colorado

Revision	Date	Description	By

- SHEET NOTES:**
- NEW HIGH PRESSURE STEAM METER IN TUNNEL. WIRE TO NEW KEP PANEL.
 - REPLACE 4" DOMESTIC WATER METER TO REMAIN. WIRE TO NEW KEP PANEL.
 - NEW CHILLED WATER METER AND SENSORS IN TUNNEL. WIRE TO NEW KEP PANEL.
 - NEW KEP PANEL WIRED TO ANDOVER SYSTEM.
 - EXISTING ANDOVER CONTROL PANELS.
 - REMOTE STEAM METER HEAD LOCATION. MOUNT 36" ABOVE TUNNEL FLOOR.
 - RE-INSULATE 10FT 8" HPS AT TUNNEL STREET ENTRY.

- GENERAL NOTES:**
- FOR DRAWING CLARITY NOT ALL PIPING AND EQUIPMENT HAS NOT BEEN SHOWN.
 - FIELD VERIFY EXISTING CONDITIONS BEFORE COMMENCEMENT OF WORK OR ORDERING MATERIALS.



BID SET

Ulteig
 Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
 9777 Pyramid Court #200
 Englewood, Colorado 80112
 Phone: 720.873.5700 Fax: 720.873.5701
 Web: www.ulteig.com
 Drawn By: JJB
 Checked By: NHM
 Approved By: NHM

MUENZINGER BUILDING

MECHANICAL/PLUMBING METERING INFORMATION MATRIX											
METER SYSTEM	MANUFACTURER	MODEL NO.	SERIAL NO.	PIPE/LINE SIZE (INCHES)	METER SIZE (INCHES)	CAPACITY (FLOW RANGE)	INSTALLATION DATE	OLD METER READING	NEW METER READING	METER LOCATION	REMARKS
DOMESTIC COLD WATER AREA "A"	ONICON	F-3100		2	2	1.0-345				NI B45	1, 2, 3
STEAM CONDENSATE AREA "A"	CADILLAC	CG-F		1 1/2	1	0-6,500				N1 B45	1, 2, 3
STEAM CONDENSATE AREA "B"	CADILLAC	CG-F		1 1/2	1	0-6,500				TUNNEL TI-Y	1, 2, 3
CHILLED WATER AREA "B"	ONICON	F-3500		3	2	13.8-295				TUNNEL TI-Y	1, 2, 3

GENERAL NOTES:
 1. SERIAL NUMBER AND INSTALLATION DATE COLUMN FOR EACH METER SHALL BE COMPLETED BY CONTRACTOR FOLLOWING METER INSTALLATION AND PRIOR TO TURN OVER TO UNIVERSITY.
 2. PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
 3. MOUNT METER HORIZONTALLY.
 4. MOUNT METER VERTICALLY.
 5. REMOTE SENSOR HEAD LOCATION.

SHEET NOTES:

- 1 NEW GRAVITY CONDENSATE METER. WIRE TO NEW KEP PANEL.
- 2 NEW DOMESTIC WATER METER. WIRE TO NEW KEP PANEL.
- 3 REPLACE AND RE-INSTALL CHILLED WATER METER. WIRE TO NEW KEP PANEL.
- 4 NEW KEP PANEL.
- 5 EXISTING AND/OVER CONTROL PANELS.
- 6 INSULATE 10FT HPS

GENERAL NOTES:

- 1. FOR DRAWING CLARITY NOT ALL PIPING AND EQUIPMENT HAS NOT BEEN SHOWN.
- 2. FIELD VERIFY EXISTING CONDITIONS BEFORE COMMENCEMENT OF WORK OR ORDERING MATERIALS.



1 AREA 'A'



1 AREA 'A'



1 AREA 'B'




2




3




5



1 IMIG MUSIC BASEMENT - AREA 'A'



1 IMIG MUSIC BASEMENT - AREA 'B'



KEY PLAN

BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
 9777 Pyramid Court #200
 Englewood, Colorado 80112
 Phone: 720.873.5700 Fax: 720.873.5701
 Web: www.ulteig.com
 Drawn By: JJB
 Checked By: NHM
 Approved By: NHM

IMIG MUSIC BUILDING

**SMART GRID
METERING 2011**
University of Colorado at Boulder
Boulder, Colorado

Revision Date Description By

MECHANICAL/PLUMBING METERING INFORMATION MATRIX											
METER SYSTEM	MANUFACTURER	MODEL NO.	SERIAL NO.	PIPE/LINE SIZE (INCHES)	METER SIZE (INCHES)	CAPACITY (FLOW RANGE)	INSTALLATION DATE	OLD METER READING	NEW METER READING	METER LOCATION	REMARKS
DOMESTIC COLD WATER	ONICON	F-3100		3	3	2.3-761					1, 2, 3
HIGH PRESSURE STEAM	VERIS	ACCELABAR		6	6	0.58-2,500					1, 2, 3
CHILLED WATER	F-3500	F-3500		12	12	35-7.050					1, 2, 3

GENERAL NOTES:
 1. SERIAL NUMBER AND INSTALLATION DATE COLUMN FOR EACH METER SHALL BE COMPLETED BY CONTRACTOR FOLLOWING METER INSTALLATION AND PRIOR TO TURN OVER TO UNIVERSITY.
 2. PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
 3. MOUNT METER HORIZONTALLY.
 4. MOUNT METER VERTICALLY.
 5. REMOTE SENSOR HEAD LOCATION.

SHEET NOTES:

- ① REPLACE STEAM METER. WIRE TO NEW KEP PANEL.
- ② REPLACE DOMESTIC WATER METER. WIRE TO NEW KEP PANEL. PROVIDE PLUG WITH CHAIN FOR EXISTING BALL VALVE.
- ③ REMOVE AND PLUG CHILLED WATER SENSOR AND CONTROLLER.
- ④ NEW KEP PANEL.
- ⑤ EXISTING AND/OVER CONTROL PANELS.
- ⑥ NEW CHILLED WATER METER SENSOR AT LOCATION SHOWN.

GENERAL NOTES:


1. FOR DRAWING CLARITY NOT ALL PIPING AND EQUIPMENT HAS NOT BEEN SHOWN.
2. FIELD VERIFY EXISTING CONDITIONS BEFORE COMMENCEMENT OF WORK OR ORDERING MATERIALS.



①



②





③




⑤



⑥



KEY PLAN



BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
 9777 Pyramid Court #200
 Englewood, Colorado 80112
 Phone: 720.873.5700 Fax: 720.873.5701
 Web: www.ulteig.com
 Drawn By: JJB
 Checked By: NHM
 Approved By: NHM

PORTER BUILDING

Project Number: 10.01461
 Date: 07/08/2011
 Sheets: 8 of 19


M6.0

HIGH PRESSURE STEAM METER DATA SCHEDULE

METER SIZE (DIA) (IN)	MANUFACTURER	MODEL NO.	SYSTEM SERVED	VERABAR SENSOR	FLOW RATE RANGE @150 PSI (PPH x 1000)	CONNECTION FLANGE (LBS)	BOLTS (PER FLANGE)			NUTS (PER FLANGE)			RING GASKET			ELECTRICAL				DIMENSIONAL DATA				REMARKS			
							TOTAL QTY	GRADE	SIZE (DIAxPITCHxLENGTH)	TOTAL QTY	GRADE	SIZE (DIAxPITCH)	DIA (IN)	THICKNESS (MM)	QTY	INNER RING	OUTER RING	UNITS MEASURED	VOLTAGE (VDC)	OUTPUT (MA)	COMMUNICATION	FACE TO FACE "L" (IN)	FLG DIA "D" (IN)		OVERALL HEIGHT "H" (IN)	OVERALL HEIGHT "H1" (IN)	WEIGHT (LBS)
2	VERIS	ACCELABAR	STEAM	-05 1/2"	0.071-1.0	300	8	8	5/8"x11 UNCx3"	8	8	5/8"x11 UNC	4 3/8	4.5	2	SERIES WOUND 304 SS	CARBON STEEL	LBS/HR	24	4 - 20	MODBUS RS485 RTU	8.875	6.5	12.0	7.5	30	1,2,3,4
3	VERIS	ACCELABAR	STEAM	-05 1/2"	0.17-7.1	300	8	8	3/4"x10 UNCx3 1/2"	8	8	3/4"x10 UNC	5 7/8	4.5	2	SERIES WOUND 304 SS	CARBON STEEL	LBS/HR	24	4 - 20	MODBUS RS485 RTU	14.5	8.25	14.0	8.5	53	1,2,3,4
4	VERIS	ACCELABAR	STEAM	-10 1"	0.32-15.9	300	8	8	7/8"x9 UNCx3 3/4"	8	8	7/8"x9 UNC	7 1/8	4.5	2	SERIES WOUND 304 SS	CARBON STEEL	LBS/HR	24	4 - 20	MODBUS RS485 RTU	16.0	10	14.0	8.5	79	1,2,3,4
6	VERIS	ACCELABAR	STEAM	-10 1"	0.68-29.2	300	12	8	7/8"x9 UNCx4 1/4"	12	8	7/8"x9 UNC	9 7/8	4.5	2	SERIES WOUND 304 SS	CARBON STEEL	LBS/HR	24	4 - 20	MODBUS RS485 RTU	20.0	12.5	15.0	9.5	153	1,2,3,4
8	VERIS	ACCELABAR	STEAM	-10 1"	1.26-56.8	300	12	8	7/8"x9 UNCx4 3/4"	12	8	7/8"x9 UNC	12 1/8	4.5	2	SERIES WOUND 304 SS	CARBON STEEL	LBS/HR	24	4 - 20	MODBUS RS485 RTU	22.0	15.0	16.0	10.5	247	1,2,3,4
10	VERIS	ACCELABAR	STEAM	-10 1"	2.10-94.8	300	16	8	1" x8 UNCx5 1/4"	16	8	1" x8 UNC	14 1/4	4.5	2	SERIES WOUND 304 SS	CARBON STEEL	LBS/HR	24	4 - 20	MODBUS RS485 RTU	24.5	17.5	17.0	11.5	417	1,2,3,4
12	VERIS	ACCELABAR	STEAM	-10 1"	2.93-126.4	300	16	8	1 1/8"x7 UNCx5 3/4"	16	8	1 1/8"x7 UNC	16 5/8	4.5	2	SERIES WOUND 304 SS	CARBON STEEL	LBS/HR	24	4 - 20	MODBUS RS485 RTU	28.0	20.5	18.0	12.5	538	1,2,3,4

REMARKS:
 1. FLOW RATE RANGES ARE BASED ON STEAM PRESSURES OF 100 PSI.
 2. PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
 3. CONTRACTOR RESPONSIBLE FOR INSURING THAT EXISTING STEAM LINE IS PROPERLY ANCHORED TO PREVENT EXCESSIVE PIPE MOVEMENT DURING INSTALLATION OF NEW METER.
 2. COORDINATE ELECTRICAL REQUIREMENTS FOR NEW METER INSTALLATION WITH UNIVERSITY APPROVED ELECTRICAL CONTRACTOR.

Revision	Date	Description	By



KEY PLAN

BID SET

Ulteig


Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
 9777 Pyramid Court #200
 Englewood, Colorado 80112
 Phone: 720.873.5700 Fax: 720.873.5701
 Web: www.ulteig.com
 Drawn By: JJB
 Checked By: NHM
 Approved By: NHM

MECHANICAL DETAILS

Revision	Date	Description	By

CHILLED WATER METER DATA SCHEDULE											
SERVICE SIZE (INCHES)	MANUFACTURER	MODEL NO.	SYSTEM SERVED	TYPE	MATERIAL		ELECTRICAL			FLOW RATE RANGE (GPM)	REMARKS
					WETTED METAL COMPONENTS	SENSOR HEAD	UNITS MEASURED	VOLTAGE (VDC)	OUTPUT (MA)		
2-2.5	ONICON	F-3500	CHILLED WATER	INSERTION ELECTROMAGNETIC	316 STAINLESS SYEEL	POLYPROPOLYNE	BTUH	24	4 - 20	2.5-230	1,2
3	ONICON	F-3500	CHILLED WATER	INSERTION ELECTROMAGNETIC	316 STAINLESS SYEEL	POLYPROPOLYNE	BTUH	24	4 - 20	6-460	1,2
4	ONICON	F-3500	CHILLED WATER	INSERTION ELECTROMAGNETIC	316 STAINLESS SYEEL	POLYPROPOLYNE	BTUH	24	4 - 20	10-800	1,2
6	ONICON	F-3500	CHILLED WATER	INSERTION ELECTROMAGNETIC	316 STAINLESS SYEEL	POLYPROPOLYNE	BTUH	24	4 - 20	15-1,800	1,2
8	ONICON	F-3500	CHILLED WATER	INSERTION ELECTROMAGNETIC	316 STAINLESS SYEEL	POLYPROPOLYNE	BTUH	24	4 - 20	39-3,100	1,2
10	ONICON	F-3500	CHILLED WATER	INSERTION ELECTROMAGNETIC	316 STAINLESS SYEEL	POLYPROPOLYNE	BTUH	24	4 - 20	61-4,900	1,2
12	ONICON	F-3500	CHILLED WATER	INSERTION ELECTROMAGNETIC	316 STAINLESS SYEEL	POLYPROPOLYNE	BTUH	24	4 - 20	87-7,050	1,2


REMARKS:
1. PER UCB STANDARDS; CONTRACTOR SHALL CONTACT THE REQUIRED UNIVERSITY DEPARTMENTS FOR INSPECTION OF WORK PRIOR TO COMPLETION OF PROJECT.
2. COORDINATE ELECTRICAL REQUIREMENTS FOR NEW METER INSTALLATION WITH UNIVERSITY APPROVED ELECTRICAL CONTRACTOR.



1
M7.1 SCALE: NONE
CHILLED WATER -
INSERTION BTU METER DETAIL

DETAIL NOTES:

- CONNECT FACTORY WIRES TO FIELD WIRES IN APPROPRIATE JUNCTION BOX.
- ALLOW ENOUGH SLACK IN THE FLEXIBLE CONDUIT TO PERMIT THE METER TO BE REMOVED FROM THE VALVE.
CLEARANCE REQUIRED FOR INSTALLATION. TYPICALLY 30" - 36" DEPENDING ON PIPE SIZE AND HEIGHT OF THE VALVE ASSEMBLY.




2
M7.1 SCALE: NONE
CHILLED WATER -
INSERTION BTU METER DETAIL

DETAIL NOTES:


- CONNECT FACTORY WIRES TO FIELD WIRES IN APPROPRIATE JUNCTION BOX.
- ALLOW ENOUGH SLACK IN THE FLEXIBLE CONDUIT TO PERMIT THE METER TO BE REMOVED FROM THE VALVE.
CLEARANCE REQUIRED FOR INSTALLATION. TYPICALLY 30" - 36" DEPENDING ON PIPE SIZE AND HEIGHT OF THE VALVE ASSEMBLY.

FLOW METERING COMPUTER



- NOTES:
1. DETAIL IS REFERENCING THE SPECIFIC WIRING CONFIGURATION FOR SPECIFIED METER.
2. SEE ELECTRICAL DRAWINGS FOR PROPER EQUIPMENT GROUNDING.

3
M7.1 SCALE: NONE
FLOW COMPUTER DETAIL



- NOTES:
1. FLOW COMPUTERS SHALL BE MOUNTED TOGETHER WITHIN A 16"(H)x14"(W)x8"(D) FIBERGLASS REINFORCED POLYESTER NEMA4X ENCLOSURE AS NOTED ON FLOOR PLANS
2. ENCLOSURE SHALL BE PROVIDED WITH 1, 2, 3 OR 4 CUTOUPS AS REQUIRED.

FLOW COMPUTER ENCLOSURE DETAIL

KEY PLAN

BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JJB
Checked By: NHM
Approved By: NHM

MECHANICAL DETAILS

3
M7.1 SCALE: NONE
METERING FLOW COMPUTER DETAIL/TERMINATIONS

SMART GRID METERING 2011

University of Colorado at Boulder
Boulder, Colorado






Revision	Date	Description	By

GENERAL NOTES:

- PRIOR TO REPLACING THE EXISTING METER(S), PROVIDE THE UNIVERSITY WITH A FINAL METER READING AND DATE OF READING. ALSO PROVIDE THE UNIVERSITY AN INITIAL METER READING AND DATE OF READING FOR ALL NEW METER(S).
- VERIFY THE LOCATION OF THE EXISTING IT LINES AND WORK AROUND THESE LINES SO AS NOT TO DISTURB, IMPACT OR BLOCK ACCESS TO THESE IT LINES OR DEVICES.
- COORDINATE ALL WORK AND THE ROUTING OF ALL CONDUIT SO AS NOT TO BLOCK ACCESS TO ANY ACCESS DOORS/PANELS.

SHEET NOTES:

- EXISTING METER #71A - LANDIS & GYR. REMOVE EXISTING METER AND REPLACE WITH NEW POWERLOGIC ION 8500 METER WITH MODBUS COMMUNICATION CAPABILITY AND PROGRAM METER.
- EXISTING PANELBOARD LAB. USE THE EXISTING SPARE NEW 20 A BREAKER IN SPACE 2 TO FEED NEW KEP PANEL. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- NEW KEP PANEL. PROVIDE POWER CONNECTION AND MODBUS COMMUNICATION CONNECTIONS TO THE PANEL.
- MODBUS COMMUNICATIONS. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- EXISTING ANDOVER CONTROL PANEL.
- NEW WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.
- NEW STEAM METER. PROVIDE A GENERAL CABLE # E2042S CABLE CONTINUOUS FROM THE METER TO THE KEP PANEL.
- NEW CHILLED WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.



BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

CIRES BUILDING



2 SMART GRID SCHEMATIC
E1.0 NO SCALE

3 PARTIAL ONE LINE
E1.0 NO SCALE

Project Number: 10_01461
Date: 07/08/2011
Sheets: 11 of 19

E1.0

SMART GRID METERING 2011

University of Colorado at Boulder
Boulder, Colorado


Revision	Date	Description	By
----------	------	-------------	----

GENERAL NOTES:



- PRIOR TO REPLACING THE EXISTING METER(S), PROVIDE THE UNIVERSITY WITH A FINAL METER READING AND DATE OF READING. ALSO PROVIDE THE UNIVERSITY AN INITIAL METER READING AND DATE OF READING FOR ALL NEW METER(S).
- VERIFY THE LOCATION OF THE EXISTING IT LINES AND WORK AROUND THESE LINES SO AS NOT TO DISTURB, IMPACT OR BLOCK ACCESS TO THESE IT LINES OR DEVICES.
- COORDINATE ALL WORK AND THE ROUTING OF ALL CONDUIT SO AS NOT TO BLOCK ACCESS TO ANY ACCESS DOORS/PANELS.

SHEET NOTES:

- EXISTING METER #71 - POWER MEASUREMENT 8400, AND METER #72 - POWER MEASUREMENT 8400. EXISTING METERS HAVE A MODBUS. PROVIDE SOFTWARE AND PROGRAMMING FOR THE METERS TO ALLOW MODBUS COMMUNICATION CAPABILITY.
- EXISTING PANELBOARD RB-1. UTILIZE SPARE 20 A BREAKER IN SPACE 6 TO FEED NEW KEP PANEL. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- NEW KEP PANEL. PROVIDE POWER CONNECTION AND MODBUS COMMUNICATION CONNECTIONS TO THE PANEL.
- MODBUS COMMUNICATIONS. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- EXISTING ANDOVER CONTROL PANEL.
- EXISTING METER #73 - LANDIS & GYR. REMOVE EXISTING METER AND REPLACE WITH NEW POWERLOGIC ION 8600 METER WITH MODBUS COMMUNICATION CAPABILITY AND PROGRAM METER.
- NEW WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.
- NEW STEAM METER. PROVIDE A GENERAL CABLE # E2042S CABLE CONTINUOUS FROM THE METER TO THE KEP PANEL.
- NEW CHILLED WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.




1 EKELEY SECOND BASEMENT LEVEL
E2.0
0' 4' 8' 16'



KEY PLAN

2 SMART GRID SCHEMATIC
E2.0 NO SCALE



3 PARTIAL ONE LINE
E2.0 NO SCALE

BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

EKELEY BUILDING

Project Number: 10_01461
Date: 07/08/2011
Sheets: 12 of 19

E2.0

SMART GRID
METERING 2011
University of Colorado at Boulder
Boulder, Colorado


Revision	Date	Description	By
----------	------	-------------	----

GENERAL NOTES:


- A. PRIOR TO REPLACING THE EXISTING METER(S), PROVIDE THE UNIVERSITY WITH A FINAL METER READING AND DATE OF READING. ALSO PROVIDE THE UNIVERSITY AN INITIAL METER READING AND DATE OF READING FOR ALL NEW METER(S).
- B. VERIFY THE LOCATION OF THE EXISTING IT LINES AND WORK AROUND THESE LINES SO AS NOT TO DISTURB, IMPACT OR BLOCK ACCESS TO THESE IT LINES OR DEVICES.
- C. COORDINATE ALL WORK AND THE ROUTING OF ALL CONDUIT SO AS NOT TO BLOCK ACCESS TO ANY ACCESS DOORS/PANELS.

SHEET NOTES:



- 1 EXISTING METER #58 - LANDIS & GYR, AND METER #59 LANDIS & GYR. REMOVE EXISTING METERS AND REPLACE WITH NEW POWERLOGIC ION 8600 METERS WITH MODBUS COMMUNICATION CAPABILITY AND PROGRAM METERS.
- 2 EXISTING PANELBOARD LSB1. PROVIDE A NEW 20 A BREAKER IN SPACE 20 TO FEED NEW KEP PANEL. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- 3 NEW KEP PANEL. PROVIDE POWER CONNECTION AND MODBUS COMMUNICATION CONNECTIONS TO THE PANEL.
- 4 MODBUS COMMUNICATIONS. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- 5 EXISTING ANDOVER CONTROL PANEL.
- 6 NEW WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.
- 7 NEW STEAM METER. PROVIDE A GENERAL CABLE # E2042S CABLE CONTINUOUS FROM THE METER TO THE KEP PANEL.
- 8 NEW CHILLED WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.



1 MCDB FOURTH LEVEL BASEMENT
E3.0
0' 4' 8' 16'



BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

MCDB BUILDING

SMART GRID
METERING 2011
University of Colorado at Boulder
Boulder, Colorado


Revision	Date	Description	By

GENERAL NOTES:


- PRIOR TO REPLACING THE EXISTING METER(S), PROVIDE THE UNIVERSITY WITH A FINAL METER READING AND DATE OF READING. ALSO PROVIDE THE UNIVERSITY AN INITIAL METER READING AND DATE OF READING FOR ALL NEW METER(S).
- VERIFY THE LOCATION OF THE EXISTING IT LINES AND WORK AROUND THESE LINES SO AS NOT TO DISTURB, IMPACT OR BLOCK ACCESS TO THESE IT LINES OR DEVICES.
- COORDINATE ALL WORK AND THE ROUTING OF ALL CONDUIT SO AS NOT TO BLOCK ACCESS TO ANY ACCESS DOORS/PANELS.

SHEET NOTES:



- EXISTING METER #64 - LANDIS & GYR. AND METER #65 - LANDIS & GYR. REMOVE EXISTING METER AND REPLACE WITH NEW POWERLOGIC ION 8600 METER WITH MODBUS COMMUNICATION CAPABILITY AND PROGRAM METER.
- EXISTING PANELBOARD LPOA. PROVIDE A NEW 20 A BREAKER IN SPACE 18 TO FEED NEW KEP PANEL. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- NEW KEP PANEL. PROVIDE POWER CONNECTION AND MODBUS COMMUNICATION CONNECTIONS TO THE PANEL.
- MODBUS COMMUNICATIONS. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- EXISTING ANDOVER CONTROL PANEL.
- NEW WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.
- NEW STEAM METER. PROVIDE A GENERAL CABLE # E2042S CABLE CONTINUOUS FROM THE METER TO THE KEP PANEL.
- NEW CHILLED WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.



2 SMART GRID SCHEMATIC
E4.0 NO SCALE



3 PARTIAL ONE LINE
E4.0 NO SCALE



BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

MUENZINGER
BUILDING

1 MUENZINGER SECOND BASEMENT LEVEL
E4.0
0' 4' 8' 16'

Project Number: 10.01461
Date: 07/08/2011
Sheets: 14 of 19

E4.0

**SMART GRID
METERING 2011**
University of Colorado at Boulder
Boulder, Colorado


Revision	Date	Description	By

GENERAL NOTES:

- A. PRIOR TO REPLACING THE EXISTING METER(S), PROVIDE THE UNIVERSITY WITH A FINAL METER READING AND DATE OF READING. ALSO PROVIDE THE UNIVERSITY AN INITIAL METER READING AND DATE OF READING FOR ALL NEW METER(S).
- B. VERIFY THE LOCATION OF THE EXISTING IT LINES AND WORK AROUND THESE LINES SO AS NOT TO DISTURB, IMPACT OR BLOCK ACCESS TO THESE IT LINES OR DEVICES.
- C. COORDINATE ALL WORK AND THE ROUTING OF ALL CONDUIT SO AS NOT TO BLOCK ACCESS TO ANY ACCESS DOORS/PANELS.

SHEET NOTES:

- 1 EXISTING METER #92 - POWER MEASUREMENTS 6600. EXISTING METER HAS A MODBUS. PROVIDE SOFTWARE AND PROGRAMMING FOR THE METER TO ALLOW MODBUS COMMUNICATION CAPABILITY.
- 2 EXISTING PANELBOARD RA. PROVIDE A NEW 20 A BREAKER IN SPACE 38 TO FEED NEW KEP PANEL. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- 3 NEW KEP PANEL. PROVIDE POWER CONNECTION AND MODBUS COMMUNICATION CONNECTIONS TO THE PANEL.
- 4 MODBUS COMMUNICATIONS. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- 5 EXISTING ANDOVER CONTROL PANEL.
- 6 ROUTE MODBUS CONDUIT AND CABLE IN EXISTING STEAM TUNNEL. SEE AREA "A" AND AREA "B" PARTIAL PLANS FOR CONTINUATION OF CONDUIT RUN.
- 7 EXISTING TUNNEL RECEPTACLE (VERIFY EXACT LOCATION) IN SPACE 38 TO FEED NEW KEP PANEL. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- 8 APPROXIMATE LOCATION OF EXISTING PANELBOARD B LOCATED ON THE FIRST FLOOR. EXISTING CIRCUIT 19 WHICH FEEDS TUNNEL RECEPTACLES TO BE EXTENDED TO FEED NEW KEP PANEL.
- 9 NEW WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.
- 10 NEW STEAM METER. PROVIDE A GENERAL CABLE # E2042S CABLE CONTINUOUS FROM THE METER TO THE KEP PANEL.
- 11 NEW CHILLED WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.



BID SET

Ulteig
Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

IMIG MUSIC BUILDING

Project Number: 10_01461
Date: 07/08/2011
Sheets: 15 of 19

E5.0

PANELBOARD SCHEDULE PANEL - B													
MOUNTING - Flush						TYPE - Square D Type NOOB							
120/208 VOLT 3 PHASE 4 WIRE						225 AMP BUS							
100 AMP MAIN BREAKER						SHORT CIRCUIT RATING							
LOCATION - MUSIC BUILDING													
CIRCUIT DESCRIPTION	RECP	LTG	MTR	MISC	CCT NUM	BRKR AMPS P	BRKR AMPS P	CCT NUM	MISC	MTR	LTG	RECP	DESCRIPTION
Lights Rm 146	256				1	20	1	A	20	1	2	1080	Receptacles
Lights Rm 143 144	384				3	20	1	B	20	1	4	1080	Receptacles
Lights Rm 140 141	384				5	20	1	C	20	1	6	1080	Receptacles
Entry Track Lights	1000				7	20	1	A	20	1	8	1080	Receptacles
Entry Lights	384				9	20	1	B	20	1	10	1080	Receptacles
Lights Rm 103	256				11	20	1	C	20	1	12	1080	Receptacles
Lights Rm 104 104A 103A	256				13	20	1	A	20	1	14	1080	Receptacles
Lights Rm 102	256				15	20	1	B	20	1	16	750	Fire Alarm
Lights Rm 102A vault Tele Rm	256				17	20	1	C	20	1	18	1080	Tunnel Lts
Tunnel Recept & KEP Panel	360			20	19	20	1	A	20	1	20	696	Hot Water Pump
Poles W Entry	500				21	20	1	B	20	1	22	512	Lights Rm 102C 108C
Exhaust Fans Bath Rms			300		23	20	1	C	20	1	24	1080	Receptacles
Receptacle	1080				25	20	1	A	20	1	26	1080	Receptacles
Unknown			1000		27	20	1	B	20	1	28	1000	Unknown
Track Lts	1000				29	20	1	C	20	1	30	1000	Track Light
Lighting 125	256				31	20	1	A	20	1	32	180	Podium Receptacle
Receptacle	1080				33	20	1	B	20	1	34	1080	Receptacles
Receptacle	1080				35	20	1	C	20	1	36	1080	Receptacles
Andover Control			750		37	20	1	A	20	1	38	1080	Receptacles
Evap Pump			696		39	20	1	B	20	1	40	696	Evap Pump
Evap Pump			696		41	20	1	C	20	1	42	696	Evap Pump


DEMAND LOAD CALCULATION											
PHASE	LOAD	%	BTWN	%	LOAD	PF CORR	DEMAND LOAD				
RECEPTACLE	7708	5844	7296	20848	10000	100%	10,000.00				
LIGHTING	256	512	1256	2024	10848	100%	10,848.00				
MOTOR	696	1392	1692	3780		X 1.00	5,424.00				
MISC	770	2750	0	3520		X 0.50	5,424.00				
TOTALS	9430	10488	10244		2024	95%	2,130.53				
					696	90%	773.33				
					3084	90%	3,426.67				
					3520	100%	3,520.00				
					TOTALS		30.17 KVA				
					CONNECTED LOAD		26.00 KVA				
					DEMAND LOAD		72.17 AMPS				
					REQUIRED AMPERAGE						

PHASE BALANCING											
PHASE	LOAD	%	BTWN	%							
A	9430	31.25	A - B	10.17							
B	10488	34.79	A - C	7.95							
C	10244	33.95	B - C	2.48							
TOTALS	30172	100.00									


PANELBOARD SCHEDULE PANEL - RA													
MOUNTING - Surface						TYPE - GTE Sylvania							
120/208 VOLT 3 PHASE 4 WIRE						225 A AMP BUS							
100 AMP MAIN BREAKER						SHORT CIRCUIT RATING							
LOCATION - MUSIC BUILDING													
CIRCUIT DESCRIPTION	RECP	LTG	MTR	MISC	CCT NUM	BRKR AMPS P	BRKR AMPS P	CCT NUM	MISC	MTR	LTG	RECP	DESCRIPTION
Receptacle	1080				1	20	1	A	20	1	2	1176	Med Evap Cooler
Receptacle	1260				3	20	1	B	20	1	4	1080	Receptacle
Receptacle	1080				5	20	1	C	20	1	6	1260	Receptacle
Receptacle	1080				7	20	1	A	20	1	8	1080	Receptacle
Receptacle	1260				9	20	1	B	20	1	10	1176	Unit Heater
Receptacle	1260				11	20	1	C	20	1	12	1176	Hot Water Circ Pump
Plugmold	1200				13	20	1	A	20	1	14	1260	Plugmold
Plugmold	1260				15	20	1	B	20	1	16	1260	Plugmold
Outlets Slage	720				17	20	1	C	20	1	18	100	Elevator Pit and Control
Plugmold	1260				19	20	1	A	20	1	20	720	TV Panel
Plugmold	1260				21	20	1	B	20	1	22	1176	Med Evap Cooler
Drink Cooler	500				23	20	1	C	20	1	24	1000	Fire Alarm NAC Panel
Receptacles	1080				25	20	1	A	20	1	26	1000	Time Clock
Receptacles	1260				27	20	1	B	20	1	28	1000	Johnson Control Panel
Unit Heater Fan			1176		29	20	1	C	20	1	30	1800	Heat Tape
Plugmold	1260				31	20	1	A	20	1	32	1800	Heat Tape
Plugmold	1260				33	20	1	B	20	1	34	750	NW Sign (breaker off)
Printer Receptacle	500				35	20	1	C	20	1	36	1620	Unknown
Plugmold	1260				37	20	1	A	20	1	38	20	KEP Panel
Plugmold	1260				39	20	1	B	20	1	40	1260	Plugmold
Unit Heater	1260				41	20	1	C	20	1	42	500	Printer Receptacle

DEMAND LOAD CALCULATION											
PHASE	LOAD	%	BTWN	%	LOAD	PF CORR	DEMAND LOAD				
RECEPTACLE	11280	12420	7800	31500	10000	100%	10,000.00				
LIGHTING	0	750	0	750	21900	100%	21,900.00				
MOTOR	1176	2352	3528	7056		X 1.00	10,750.00				
MISC	2820	1000	2900	6720		X 0.50	10,750.00				
TOTALS	15276	16522	14228		750	95%	789.47				
					1176	90%	1,306.67				
					5880	90%	6,533.33				
					6720	100%	6,720.00				
					TOTALS		46.03 KVA				
					CONNECTED LOAD		36.62 KVA				
					DEMAND LOAD		101.66 AMPS				
					REQUIRED AMPERAGE						


PHASE BALANCING											
PHASE	LOAD	%	BTWN	%							
A	15276	33.19	A - B	7.54							
B	16522	35.30	A - C	7.37							
C	14228	30.91	B - C	16.12							
TOTALS	46026	100.00									




IMIG MUSIC BASEMENT - AREA 'A'
E5.0 NO SCALE



IMIG MUSIC BASEMENT - AREA 'B'
E5.0 NO SCALE



4 PARTIAL ONE LINE
E5.0 NO SCALE



3 SMART GRID SCHEMATIC
E5.0 NO SCALE

**SMART GRID
METERING 2011**
University of Colorado at Boulder
Boulder, Colorado


Revision	Date	Description	By

GENERAL NOTES:


- A. PRIOR TO REPLACING THE EXISTING METER(S), PROVIDE THE UNIVERSITY WITH A FINAL METER READING AND DATE OF READING. ALSO PROVIDE THE UNIVERSITY AN INITIAL METER READING AND DATE OF READING FOR ALL NEW METER(S).
- B. VERIFY THE LOCATION OF THE EXISTING IT LINES AND WORK AROUND THESE LINES SO AS NOT TO DISTURB, IMPACT OR BLOCK ACCESS TO THESE IT LINES OR DEVICES.
- C. COORDINATE ALL WORK AND THE ROUTING OF ALL CONDUIT SO AS NOT TO BLOCK ACCESS TO ANY ACCESS DOORS/PANELS.

SHEET NOTES:


- 1 EXISTING METER #62 - POWER MEASUREMENTS 8600. EXISTING METER HAS A MODBUS. PROVIDE SOFTWARE AND PROGRAMMING FOR THE METER TO ALLOW MODBUS COMMUNICATION CAPABILITY.
- 2 EXISTING PANELBOARD 1PBB. PROVIDE A NEW 20 A BREAKER IN SPACE 18 TO FEED NEW KEP PANEL. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- 3 NEW KEP PANEL. PROVIDE POWER CONNECTION AND MODBUS COMMUNICATION CONNECTIONS TO THE PANEL.
- 4 MODBUS COMMUNICATIONS. ROUTE CONDUIT APPROXIMATELY AS SHOWN TO MINIMIZE ASBESTOS CONCERNS. COORDINATE EXACT CONDUIT ROUTING WITH EH&S.
- 5 EXISTING ANDOVER CONTROL PANEL.
- 6 EXISTING SIEMENS METER TO REMAIN AS IS.
- 7 EXISTING METER #61 - LANDIS & GYR. REMOVE EXISTING METER AND REPLACE WITH NEW POWERLOGIC ION 8600 METER WITH MODBUS COMMUNICATION CAPABILITY AND PROGRAM METERS.
- 8 NEW WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.
- 9 NEW STEAM METER. PROVIDE A GENERAL CABLE # E2042S CABLE CONTINUOUS FROM THE METER TO THE KEP PANEL.
- 10 NEW CHILLED WATER METER. PROVIDE TWO GENERAL CABLE # E2042S CABLES CONTINUOUS FROM THE METER TO THE KEP PANEL.




1 PORTER SECOND BASEMENT LEVEL - AREA 'A'
E6.0




2 PORTER SECOND BASEMENT LEVEL - AREA 'B'
E6.0



4 PARTIAL ONE LINE
E6.0 NO SCALE



3 SMART GRID SCHEMATIC
E6.0 NO SCALE



KEY PLAN

BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

**PORTER
BIOSCIENCES
BUILDING**

Project Number: 10.01461
Date: 07/08/2011
Sheets: 16 of 19 **E6.0**

Revision	Date	Description	By

PANELBOARD SCHEDULE PANEL - LAB														MOUNTING - Flush	
120/208 VOLT 3 PHASE 4 WIRE														TYPE -Square D Type NQOB	
150 AMP BUS														150 A AMP MAIN BREAKER	
SHORT CIRCUIT RATING														LOCATION - CIRES	
CIRCUIT DESCRIPTION	CIRCUIT RECP	LOAD LTG	IN MTR	WATTS MISC	CCT NUM	BRKR AMPS P	BRKR AMPS P	CCT NUM	CIRCUIT MISC	LOAD MTR	IN LTG	WATTS RECP	CIRCUIT DESCRIPTION		
1080 Receptacles	1080				1	20	1	A	20	1	2	1080	KEP Panel		
1260 Receptacles	1260				3	20	1	B	20	1	4	1260	Receptacles		
1260 Receptacles	1260				5	20	1	C	20	1	6	1260	Receptacles		
HWD Controls				1000	7	20	1	A	20	1	8	1080	Receptacles		
Spare					9	20	1	B	20	1	10	1176	Evap Cooler		
Temp Control					11	20	1	C	20	1	12	1260	Receptacles		
Receptacles	1080				13	20	1	A	20	1	14	1080	Receptacles		
Air Dryer Receptacle	360				15	20	1	B	20	1	16	1260	Receptacles		
Spare					17	20	1	C	20	1	18	1080	Receptacles		
Spare					19	20	1	A	20	1	20	1260	Receptacles		
Sump Pumps			1176		21	20	1	B	20	1	22		Spare		
Spare					23	20	1	C	20	1	24		Spare		
Spare					25	20	1	A	20	1	26		Spare		
Spare					27	20	1	B	20	1	28		Spare		
Spare					29	20	1	C	20	1	30		Spare		
Space					31			A	30		32	1321	1B15 West Wall		
Space					33			B			34	1321	"		
Space					35			C			36	1321	"		
Space					37			A			38		Space		
Space					39			B			40		Space		
Space					41			C			42		Space		

DEMAND LOAD CALCULATION									
PHASE LOADING	A	B	C	TOTAL	LOAD	PF CORR	DEMAND LOAD		
RECEPTACLE	4320	3960	3780	12060	10000	100%	10,000.00 X 1.00	10,000.00	
LIGHTING	0	0	0	0	2060	100%	2,060.00 X 0.50	1,030.00	
MOTOR	1321	3673	1321	6315					
MISC	1000	0	1000	2000					
TOTALS	6641	7633	6101						

PHASE BALANCING				
LOAD	%	BTWN	%	
A	6641	32.59	A - B	13.00
B	7633	37.46	A - C	8.85
C	6101	29.94	B - C	25.11
TOTALS	20375	100.00		

PANELBOARD SCHEDULE PANEL - LSB1														MOUNTING - Surface	
120/208 VOLT 3 PHASE 4 WIRE														TYPE -GE A Series (?)	
100 A AMP BUS														100 A AMP MAIN BREAKER	
SHORT CIRCUIT RATING														LOCATION - MCDB	
900 Receptacles	900				1	20	1	A	20	1	2	900	Spare		
1080 Receptacles	1080				3	20	1	B	20	1	4	500	Compressor Drains		
PSB 26				500	5	20	1	C	20	1	6	500	Lights Mechanical		
Flow Processor				500	7	20	1	A	20	1	8	500	Lights Mechanical		
???				1000	9	20	1	B	20	1	10	500	Lights Mechanical		
Steam Condensate Station				500	11	20	1	C	20	1	12	500	Lights Mechanical		
???				1000	13	20	1	A	20	1	14	500	Lights Mechanical		
???				1000	15	20	1	B	20	1	16	1000	???		
???				1000	17	20	1	C	20	1	18	1000	???		
???				1000	19	20	1	A	20	1	20	20	???		
???				1000	21	20	1	B	20	1	22		KEP Panel		
???				1000	23	20	1	C	20	1	24		Space		
???				3866	25	60	1	A	20	1	26		Spare		
???				3866	27			B	20	1	28		Spare		
???				3866	29			C	20	1	30		Spare		

DEMAND LOAD CALCULATION									
PHASE LOADING	A	B	C	TOTAL	LOAD	PF CORR	DEMAND LOAD		
RECEPTACLE	900	1080	0	1980	1980	100%	1,980.00 X 1.00	1,980.00	
LIGHTING	1000	500	1000	2500					
MOTOR	3866	3866	3866	11598					
MISC	3020	4500	4000	11520					
TOTALS	8786	9946	8866						

PHASE BALANCING				
LOAD	%	BTWN	%	
A	8786	31.84	A - B	11.66
B	9946	36.04	A - C	0.90
C	8866	32.13	B - C	12.18
TOTALS	27598	100.00		

PANELBOARD SCHEDULE PANEL - LPOA														MOUNTING - Surface	
120/208 VOLT 3 PHASE 4 WIRE														TYPE -GE A Series	
100 AMP BUS														100 AMP MAIN BREAKER	
SHORT CIRCUIT RATING														LOCATION - MUENZINGER	
HRP - 1					1	20	1	A	20	1	2	1320	CU - RM 0041		
"					3	20	1	B	20	1	4	1320	"		
"					5	20	1	C	20	1	6	1320	"		
Space					7	20	1	A	20	1	8	500	Tunnel Receptacles		
Space					9	20	1	B	20	1	10	500	Tunnel Fan		
Glycol Feeder				1000	11	20	1	C	20	1	12	500	Tunnel Lights		
Time Clock					13	20	1	A	20	1	14	1000	Control Circuit		
Space					15	20	1	B	20	1	16		Breaker off		
Space					17	20	1	C	20	1	18	20		KEP Panel	

DEMAND LOAD CALCULATION									
PHASE LOADING	A	B	C	TOTAL	LOAD	PF CORR	DEMAND LOAD		
RECEPTACLE	720	0	0	720	720	100%	720.00 X 1.00	720.00	
LIGHTING	0	0	500	500					
MOTOR	2640	3140	3640	9420					
MISC	1500	0	20	1520					
TOTALS	4860	3140	4160						

PHASE BALANCING				
LOAD	%	BTWN	%	
A	4860	39.97	A - B	54.78
B	3140	25.82	A - C	16.83
C	4160	34.21	B - C	24.52
TOTALS	12160	100.00		


PANELBOARD SCHEDULE PANEL - 1PBB														MOUNTING - Surface	
120/208 VOLT 3 PHASE 4 WIRE														TYPE -GE NLAB	
225 AMP BUS														50 A AMP MAIN BREAKER	
SHORT CIRCUIT RATING														LOCATION - PORTER	
Spare					1	20	1	A	20	1	2		Spare		
Condensate Panel				1000	3	20	1	B	20	1	4		Spare		
Receptacle Mech Room	720				5	20	1	C	20	1	6		Spare		
Spare					7	20	1	A	20	1	8		Spare		
Spare to Cond Panel (brk off)					9	20	1	B	20	1	10	1000	Andover Panel		
Pole Lights		1500			11	20	1	C	20	1	12		Spare		
Receptacle	900				13	20	1	A	20	1	14		Spare		
Tunnel Lights		1200			15	20	1	B	20	1	16		Spare		
???				1000	17	20	1	C	20	1	18	20	KEP		
Space					19	20	1	A	20	1	20	1320	Air Compressor 20 A		
Space					21			B			22	1320	"		
Space					23			C			24	1320	"		
Space					25			A			26		Space		
Space					27			B			28		Space		
Space					29			C			30		Space		
Space					31			A			32		Space		
Space					33			B			34		Space		
Space					35			C			36		Space		
Space					37			A			38		Space		
Space					39			B			40		Space		
Space					41			C			42		Space		

DEMAND LOAD CALCULATION									
PHASE LOADING	A	B	C	TOTAL	LOAD	PF CORR	DEMAND LOAD		
RECEPTACLE	900	0	720	1620	1620	100%	1,620.00 X 1.00	1,620.00	
LIGHTING	0	1200	1500	2700					
MOTOR	1320	1320	1320	3960					
MISC	0	2000	1020	3020					
TOTALS	2220	4520	4560						


PHASE BALANCING				
LOAD	%	BTWN	%	
A	2220	19.65	A - B	50.88
B	4520	40.00	A - C	51.32
C	4560	40.35	B - C	0.88
TOTALS	11300	100.00		

PANELBOARD SCHEDULE PANEL - RB-1														MOUNTING - Surface	
120/208 VOLT 3 PHASE 4 WIRE														TYPE -Square D NQ0D	
100 A AMP BUS														50 A AMP MAIN BREAKER	
SHORT CIRCUIT RATING														LOCATION - EKELEY	
Receptacles	1080				1	20	1	A	20	1	2	500	Receiver Tank Dump Valve		
Glycol Pump				1000	3	20	1	B	20	1	4	500	Magnetic Starter Control		
Andover Panel					5	20	1	C	20	1	6	20	KEP Panel		
Spare					7	20	1	A	20	1	8		Spare		
Spare					9	20	1	B	20	1	10		Spare		
Spare					11	20	1	C	20	1	12		Spare		
Space					13			A			14		Space		
Space					15			B			16		Space		
Space					17			C			18		Space		
Space					19</										

METER 120/208VOLT CIRCUIT



METER 277/480 VOLT CIRCUIT



KEY PLAN

BID SET




Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

DETAILS


SMART GRID
METERING 2011

University of Colorado at Boulder
Boulder, Colorado

Revision	Date	Description	By




MODBUS RTU RS-485
COMMUNICATION TRUCK
E7.2 NOT TO SCALE



NOTE: POWER SUPPLY CAN BE REMOVED (WITH WRITTEN UNIVERSITY P.M. APPROVAL) IF MAG. METERS NOT INCLUDED IN UMP. KEP CAN POWER 24VDC LOOP.


PICTORIAL UTILITY METERING PANEL (UMP)
E7.2 NOT TO SCALE



- NOTES:
- FLOW COMPUTERS SHALL BE MOUNTED TOGETHER WITHIN A 16"(H)x14"(W)x8"(D) FIBERGLASS REINFORCED POLYESTER NEMA4X ENCLOSURE AS NOTED ON FLOOR PLANS
 - ENCLOSURE SHALL BE PROVIDED WITH 1, 2, 3 OR 4 CUTOUPS AS REQUIRED.

FLOW COMPUTER ENCLOSURE DETAIL


FLOW METERING COMPUTER



- FLOW METER TRANSMITTER #1 5--24 VDC
TRANSMITTER #2 5--24 VDC
- NOTES:
- DETAIL REFERENCING SPECIFIC WIRING CONFIGURATION FOR SPECIFIED METER.

FLOW COMPUTER DETAIL

METERING FLOW COMPUTER DETAIL/TERMINATIONS
E7.2 NOT TO SCALE



WIRING DIAGRAM UTILITY METERING PANEL (UMP)
E7.2 NOT TO SCALE

KEY PLAN

BID SET



Bismarck - Denver - Detroit Lakes - Fargo - Minneapolis - Sioux Falls
9777 Pyramid Court #200
Englewood, Colorado 80112
Phone: 720.873.5700 Fax: 720.873.5701
Web: www.ulteig.com
Drawn By: JPS
Checked By: RNH
Approved By: RNH

ELECTRICAL DETAILS

Project Number: 10.01461
Date: 07/08/2011
Sheets: 19 of 19

E7.2